

# HT-2000

**FAST • SAFE • RELIABLE**



## **DIELECTRIC WITHSTAND (HIPOT) 2000 VAC PRODUCTION LINE TESTER**

### **Features**

- AC Output to 2000 volts; delivers up to 20mA.
- Logic controlled, one button test. LED's indicate test progress. Upon failure, buzzer sounds and testing is terminated.
- Output voltage, leakage current limit, voltage ramp-up time and test duration are controlled from the rear panel.
- Ground continuity test is defeatable for testing of two wire products.
- Nema 5-15R receptacle provided on front panel for high voltage output.
- Automatic voltage rampdown circuit eliminates residual voltage..
- Operation instructions provided on the rear panel.
- Performs to UL, CE, IEC, CSA, TUV safety agency requirements for production line testing.
- Ergonomically designed for safety, speed and efficiency.
- Calibration resistor mounted on rear panel.
- One year calibration cycle.
- Economical, durable and compact.
- Test leads included.
- **TEST-LINK** Compatible
- 30 day trial - 1 year warranty

**COMPLIANCE  
WEST USA**  
CALL (800) 748-6224



[www.compwest.com](http://www.compwest.com)

# HT-2000



## ELECTRICAL

Output:	0-2000 Volts AC into NEMA 5-15R receptacle Pigtail and Receptacle adapters available for most configurations. Consult factory.
Leakage Current:	0-20 mA
Pass/Fail Criteria:	
Ground Continuity:	3 ohm $\pm$ 5% * (defeatable)
Leakage Current:	User adjustable 1-20 mA
Dielectric Breakdown:	Separate high frequency detection circuit for breakdown spike detection.
Test Time:	User adjustable 1-60 sec.
Voltage Ramp Time:	User adjustable .5-5 sec.
Pass/Fail Repeatability:	$\pm$ 3%
Duty Cycle:	100%
Meter Accuracy:	$\pm$ 20V (1% of Full Scale reading)
Discharge Time:	Voltage dependent; discharge progress displayed on front panel meter.
Test Adjustments:	Tamper-proof operation available.

## ENVIRONMENTAL

Operating Temperature:	15-40°C
Relative Humidity Range:	0-90% non-condensing

## GENERAL

Input Power Requirements:	Model HT-2000: 114-127 volts, 50/60 Hz
Weight:	10.5 lbs.
Dimensions:	9.250 (W) x 4.250 (H) x 10.000 (L) in.

## SAFETY

Transformer Output:	<500 VA
Visual Indication Of Voltage Output:	Provided by front panel meter, directly connected to high voltage output.
Failure Indication:	Audible, provided by internal buzzer Visual, provided by red LED's on front panel Test automatically terminated on failure.
Ground Test:	Provided; 3 ohm pass/fail point. May be defeated for testing of prod- ucts with two wire power supply cords.
Leakage Test:	Provided; 5mA factory set pass/fail point, user adjustable. 120 Kohm calibration resistor provided on rear panel.
Operation Instructions:	Provided on rear panel.