## HIPOT TESTERS / production line testers

Fa 💭

NEAST NEAFE NELLABLE

## <u>HT-3000P</u>



DIELECTRIC WITHSTAND/GROUND CONTINUITY 2000VAC / 2800 VDC with offline test time/current limit setup and viewing.

### **FEATURES**

- AC Output to 2000 volts; delivers up to 20mA.
- DC Output to 2800 volts; delivers up to 5mA.
- Logic controlled, one button test. LED's indicate test progress. Upon failure, buzzer sounds and testing is terminated.
- Output voltage, leakage current limit, voltage ramp-up time and test duration are controlled from the rear panel. Leakage current limit and test time are displayed on LED and are adjustable with high voltage output defeated.
- Ground continuity test is defeatable for testing of two wire products.
- Nema 5-15R receptacle provided on front panel for high voltage output.
- Automatic voltage rampdown circuit.

- Operation instructions provided on the rear panel.
- Performs to UL and CSA safety agency requirements for production hipot testing.
- Can be connected to our GF-30ac Ground Bond tester for complete TUV and European safety testing.
- Ergonomically designed for safety, speed and efficiency.
- Small footprint and light weight.
- Economical, durable and compact.
- Calibration Certificate included.
- Test leads included.
- TEST-LINK Compatible

The blue box that tests. And tests.

**Compliance West USA** 

www.compwest.com

#### Call [800] 748-6224

# HT-3000P





voltage receptacle, both mounted on front panel

on right above for leakage current display.)

3 ohm ± 5% \* (defeatable)

User adjustable .5-5 sec.

±2%: 500V to maximum output

100%

Pigtail and Receptacle adapters available for most configurations.

User adjustable 1-20mA AC or 1-5 mA DC in 0.1 mA increments True arc detection using separate high frequency transformer.

Progress Lights on Front Panel show test progress and results.

defeated. (See center picture above for test time display)

Immediate voltage discharge upon failure or end of test.

Provided by front panel meter, directly connected to high

Tamper-proof operation available by pulling knobs.

0-2000 Volts AC and 0-2800 Volts DC +0 -10% into NEMA 5-15R receptacle or high

1-20 mA AC or 1-5 mA DC, set using LED display with HV output defeated. (See picture

User adjustable 1-60 sec. in 1 second increments using LED display with HV output





#### ELECTRICAL M

Output:

#### Leakage Current

Pass/Fail Criteria: Ground Continuity: Leakage Current: Dielectric Breakdown: Test Time:

Voltage Ramp Time: Test Status: Duty Cycle: Meter Accuracy: **Discharge Time:** Test Adjustments:

### ENVIRONMENTAL >>

Operating Temperature:: Relative Humidity Range: 15-40°C 0-90% non-condensing

<500 VA

voltage output.



#### GENERAL 🔰

Input Power Requirements: Weight: Dimensions:

114-127 volts. 50/60 Hz 10.5 lbs.



#### SAFETY **N**

Transformer Output: Visual Indication Of Voltage Output:

Failure Indication:

**Operation Instructions:** 

Ground Test:

Leakage Test:


9.250 (W) x 4.250 (H) x 10.000 (L) in.

Audible, provided by internal buzzer

with two wire power supply cords.

Provided on rear panel.

Test automatically terminated on failure.



The hue box that tests. And tests

Compliance West USA 2120 Jimmy Durante Boulevard Suite 124 Del Mar, California 92014 USA Toll Free: [800] 748.6224 • P: [858] 481.6454 • F: [858] 481.8527 • www.compwest.com • sales@compwest.com