Data Sheet



Hipot Tester HT-10000P AC

PN:00-HT10KP ac

✤ 10KV AC Dielectric Withstand Tester.



The HT-10000P AC tester is a 10KVac hipot tester with Voltage display for easy output monitoring.

Offers defeatable ramp, arc detection and test timer settings and are adjustable on the rear panel.

Easy to set up and use. Ships complete with cables, manual, Calibration Certificate and Calibration Data Log Copy.

*Actual products may vary depending on options and configuration.

Features

- Fast accurate results.
- Microcontroller Technologies.
- One button test, easy to setup.
- LED's indicate test progress.
- Upon failure, the buzzer sounds, and testing is terminated.
- Output voltage, Test and Reset controls on front panel.
- Voltage ramp, arc detection and test timer are defeatable.
- Designed for product development and laboratory use.

- Separate arc detection circuitry.
- Supports PLC interface for complete automated testing with the **RI option**.
- Main shutdown switch on front panel.
- Ergonomically designed for safety, speed, and efficiency.
- Leads, manual and calibration certificate included.
- ISO17025 Calibration available.
- One year calibration cycle.
- One year warranty.



Data Sheet

COMPLIANCE WEST USA

The blue box that tests. And tests.

Specifications

TESTING CIRCUITRY

Test Type:	AC.
Max. Output Voltage:	10,000Vac.
Leakage Current:	10mAac, 0.1mA increments.
Breakdown Detect:	Independent High Frequency Circuit (50KHz–500KHz).
Transformer Power: Leakage Current Detect:	<500VA. Independent Low Frequency Circuit.
Leakage Current Detect.	Independent Low Trequency Circuit.
Ramp Time Range:	1-5 Seconds.
Test Time Range:	1-60 Seconds.
Display:	4 Digits LED Display. ± 0.1KVac full scale.
Voltage Meter Accuracy: Leakage Accuracy:	\pm 0.1KVac full scale. \pm 0.1mA full scale.
Leakage Accuracy.	
Duty Cycle:	100%; Continuous.
Pass/Fail Repeatability:	±3%
ELECTRICAL	
Rated Input Voltage:	120Vac. 220,230V optional
Frequency:	50/60Hz.
Fuse:	2A, 250V, time delay, 5x20mm.
SAFETY	
Safety Interlock:	2-pin terminal block on rear panel; shorted for operation. (Optional)
Output Voltage Indicator:	Front panel meter directly connected to High Voltage.
Failure Indicator:	Visual; provided by red LED's, Audible; provided by buzzer.
	Test automatically terminated on failure.
OUTPUTS	
HV:	High Voltage output.
RETURN:	4mm Socket (XEF-1RR), 1000V, CAT IV, 24A, Black.

Environmental

Operating Temperature: Relative Humidity Range: 15-40°C. 0-90% non-condensing.



Data Sheet

COMPLIANCE WEST USA

The blue box that tests. And tests.

General

Dimensions:	10" wide x 5" high x 12" deep.
Weight:	18lbs approx.
Product Package:	 HT10000VP AC Tester. HT10000P AC User Manual. H.V Test lead. Ground Test Lead. Power Cord. NIST traceable calibration certificate to ANSI Z540.

Calibration Data Copy.

> Options

00-RI:	Relay Interface/PLC Interface. Test signals through relay contacts/coils.
00-XI:	External Safety Interlock.
00-AR:	Auto Reset on Pass.
00-VF:	Voltage Hold on Failure.
00-RF:	Continuous Operation, Timer/Always operation.
00-220:	220V mains input.
00-230:	230V mains input.

Rev 8.1

